Location: 19.0.1C Date: 08-01-2021

Contract:

SN:

11

11

Engineer: Study Case: LF Revision: Base

Filename: NEW\_PSA Config.: Normal

### **Electrical Transient Analyzer Program**

### **Load Flow Analysis**

Loading Category (1): Design

Generation Category (1): Design

Load Diversity Factor: None

	Swing	V-Control	Load	Total			
Number of Buses:	1	0	8	9			
				Line/Cable/			
	XFMR2	XFMR3	Reactor	Busway	Impedance	Tie PD	

Method of Solution: Adaptive Newton-Raphson Method

0

Maximum No. of Iteration: 99

Number of Branches:

Precision of Solution: 0.0001000

System Frequency: 50.00 Hz
Unit System: English

Project Filename: NEW\_PSA

Output Filename: C:\ETAP 1901\NEW\_PSA\Untitled.lfr

 Project:
 ETAP
 Page:
 2

 Location:
 19.0.1C
 Date:
 08-01-2021

Contract: SN:

Engineer: Study Case: LF Revision: Base

Filename: NEW\_PSA Config.: Normal

# Adjustments

Tolerance	Apply Adjustments	Individual /Global	Percent
Transformer Impedance:	Yes	Individual	
Reactor Impedance:	Yes	Individual	
Overload Heater Resistance:	No		
Transmission Line Length:	No		
Cable / Busway Length:	No		
Temperature Correction	Apply Adjustments	Individual /Global	Degree C
Transmission Line Resistance:	Yes	Individual	
Cable / Busway Resistance:	Yes	Individual	

Location: 19.0.1C Date: 08-01-2021

Contract:

Engineer:

Filename:

NEW\_PSA

SN:

Study Case: LF Revision: Base

Config.: Normal

## **Bus Input Data**

					Load							
Bus			Initial Voltage		Consta	Constant kVA		nnt Z	Cons	ant I	Gen	eric
ID	kV	Sub-sys	% Mag.	Ang.	MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar
Bus1	11.000	1	103.0	0.0								
Bus 2	11.000	1	100.0	0.0	10.000	5.000						
Bus 3	11.000	1	100.0	0.0	25.000	15.000						
Bus 4	11.000	1	100.0	0.0	60.000	40.000						
Bus 5	11.000	1	100.0	0.0	10.000	5.000						
Bus 6	11.000	1	100.0	0.0	100.000	80.000						
Bus 7	11.000	1	100.0	0.0	80.000	60.000						
Bus 8	11.000	1	100.0	0.0	40.091	20.039						
Bus 9	11.000	1	100.0	0.0	16.000	8.000	4.000	2.000				
Total Number of Buses: 9					341.091	233.039	4.000	2.000	0.000	0.000	0.000	0.000

Bus1 11.000 Swing 1			Volta	ge	Generation			Mvar Limits		
ID	kV	Type	Sub-sys	% Mag.	Angle	MW	Mvar	% PF	Max	Min
Bus1	11.000	Swing	1	103.0	0.0					
Bus 5	11.000	Mvar/PF Control	1	100.0	0.0	80.000	94.118	64.8		
						80.000	94.118			

Project: ETAP Page: 4 19.0.1C Location: Date: 08-01-2021 Contract:

SN:

Engineer: Revision: Base Study Case: LF Filename: NEW\_PSA

Config.: Normal

### **Impedance Input Data**

Impedance	Positive S	Sequence Imp	pedance	
ID	R	X	Y	Unit
Z1	1.8	5.4	0.9	% in 11.000 kV base and 100.0 MVA base
Z2	1.8	5.6	0	% in 11.000 kV base and 100.0 MVA base
Z3	1.5	4.5	0.76	% in 11.000 kV base and 100.0 MVA base
Z4	1.3	3.6	0.6	% in 11.000 kV base and 100.0 MVA base
Z5	2	6.6	0	% in 11.000 kV base and 100.0 MVA base
Z6	1	5	0	% in 11.000 kV base and 100.0 MVA base
Z7	1.4	3.6	0.6	% in 11.000 kV base and 100.0 MVA base
Z8	3.2	7.6	0	% in 11.000 kV base and 100.0 MVA base
Z10	2	6	0	% in 11.000 kV base and 100.0 MVA base
Z11	2.2	6.5	0	% in 11.000 kV base and 100.0 MVA base
Z12	6	3	0.56	% in 11.000 kV base and 100.0 MVA base

Location: 19.0.1C Date: 08-01-2021

SN:

Contract:

Engineer: Study Case: LF Revision: Base

Filename: NEW\_PSA Config.: Normal

## **Branch Connections**

CKT/E	Branch	Cor	nnected Bus ID	% Impe	% Impedance, Pos. Seq., 100 MVA Base						
ID	Туре	From Bus	To Bus	R	X	Z	Y				
Z1	Impedance	Busl	Bus 2	1.80	5.40	5.69	0.9000000				
Z2	Impedance	Bus 2	Bus 3	1.80	5.60	5.88					
Z3	Impedance	Bus 4	Bus1	1.50	4.50	4.74	0.7600000				
Z4	Impedance	Bus 5	Bus 4	1.30	3.60	3.83	0.6000000				
Z5	Impedance	Bus 4	Bus 6	2.00	6.60	6.90					
Z6	Impedance	Bus 6	Bus 9	1.00	5.00	5.10					
Z7	Impedance	Bus 5	Bus 7	1.40	3.60	3.86	0.6000000				
Z8	Impedance	Bus 7	Bus 8	3.20	7.60	8.25					
Z10	Impedance	Bus 9	Bus 3	2.00	6.00	6.32					
Z11	Impedance	Bus 8	Bus 9	2.20	6.50	6.86					
Z12	Impedance	Bus 5	Bus 6	6.00	3.00	6.71	0.5600000				

Location: 19.0.1C Date: 08-01-2021

SN:

Contract:

Engineer: Study Case: LF Revision: Base

Filename: NEW\_PSA Config.: Normal

## LOAD FLOW REPORT

	Bus		Volt	age	Gener	ration	Lo	ad	d Load Flow						XFMR
II	)	kV	% Mag.	Ang.	MW	Mvar	MW	Mvar		ID	MW	Mvar	Amp	%PF	%Tap
* Bus1		11.000	103.000	0.0	283.033	187.938	0.000	0.000	Bus 2		90.185	64.213	5641.5	81.5	
									Bus 4		192.848	123.725	11675.6	84.2	
Bus 2		11.000	98.098	-2.1	0.000	0.000	10.000	5.000	Bus1		-88.095	-58.854	5668.5	83.2	
									Bus 3		78.095	53.854	5075.6	82.3	
Bus 3		11.000	93.655	-4.2	0.000	0.000	25.000	15.000	Bus 2		-76.412	-48.617	5075.6	84.4	
									Bus 9		51.412	33.617	3442.5	83.7	
Bus 4		11.000	94.999	-4.0	0.000	0.000	60.000	40.000	Bus1		-185.411	-102.160	11695.9	87.6	
									Bus 5		69.570	6.306	3859.5	99.6	
									Bus 6		55.841	55.855	4363.6	70.7	
Bus 5		11.000	93.833	-5.5	80.000	94.118	10.000	5.000	Bus 4		-68.867	-4.893	3861.9	99.7	
									Bus 7		89.073	73.454	6458.0	77.2	
									Bus 6		49.794	20.557	3013.3	92.4	
Bus 6		11.000	89.984	-5.7	0.000	0.000	100.000	80.000	Bus 4		-54.458	-51.293	4363.6	72.8	
									Bus 9		2.268	-8.669	522.7	-25.3	
									Bus 5		-47.809	-20.038	3023.7	92.2	
Bus 7		11.000	89.705	-7.0	0.000	0.000	80.000	60.000	Bus 5		-86.947	-68.493	6476.1	78.6	
									Bus 8		6.947	8.493	642.0	63.3	
Bus 8		11.000	88.738	-7.2	0.000	0.000	40.091	20.039	Bus 7		-6.899	-8.379	642.0	63.6	
									Bus 9		-33.192	-11.659	2080.8	94.3	
Bus 9		11.000	90.441	-5.9	0.000	0.000	19.272	9.636	Bus 6		-2.258	8.719	522.7	-25.1	
									Bus 3		-50.552	-31.036	3442.5	85.2	
									Bus 8		33.537	12.681	2080.8	93.5	

<sup>\*</sup> Indicates a voltage regulated bus ( voltage controlled or swing type machine connected to it)

<sup>#</sup> Indicates a bus with a load mismatch of more than 0.1 MVA

Location: 19.0.1C Date: 08-01-2021

Contract:

SN:

61.254

86.2

3554.8

Engineer: Study Case: LF Revision: Base

Config.: Normal

### **Bus Loading Summary Report**

### **Directly Connected Load Total Bus Load** Bus Constant kVA Constant Z Constant I Generic Percent kV Mvar MW MW MW Mvar MW Mvar Mvar MVA ID Rated Amp % PF Loading Amp Bus1 11.000 339.747 17312.7 83.3 Bus 2 11.000 10.000 5.000 105.946 83.2 5668.5 Bus 3 11.000 25.000 15.000 90.567 84.4 5075.6 Bus 4 11.000 60.000 40.000 211.693 87.6 11695.9 Bus 5 11.000 10.000 5.000 178.786 83.3 10000.6 11.000 100.000 80.000 7573.4 Bus 6 129.841 78.8 Bus 7 11.000 80.000 60.000 110.685 78.6 6476.1 Bus 8 11.000 40.091 20.039 44.820 89.4 2651.0

1.636

16.000

8.000

3.272

11.000

Filename:

Bus 9

 $NEW\_PSA$ 

<sup>\*</sup> Indicates operating load of a bus exceeds the bus critical limit (100.0% of the Continuous Ampere rating).

<sup>#</sup> Indicates operating load of a bus exceeds the bus marginal limit (95.0% of the Continuous Ampere rating).

Project:		ETAP	Page:	8
Location:		19.0.1C	Date:	08-01-2021
Contract:			SN:	
Engineer:		Study Case: LF	Revision:	Base
Filename:	NEW_PSA	Stady Case. 21	Config.:	Normal

## **Branch Losses Summary Report**

	From-To	From-To Bus Flow		To-From Bus Flow Lo		sses	% Bus Voltage		Vd % Drop
Branch ID	MW	MW Mvar		Mvar	kW	kvar	From	То	in Vmag
Z1	90.185	64.213	-88.095	-58.854	2090.0	5359.5	103.0	98.1	4.90
Z10	51.412	33.617	-50.552	-31.036	860.4	2581.1	93.7	90.4	3.21
Z11	-33.192	-11.659	33.537	12.681	345.8	1021.6	88.7	90.4	1.70
Z12	49.794	20.557	-47.809	-20.038	1984.6	519.0	93.8	90.0	3.85
Z2	78.095	53.854	-76.412	-48.617	1683.2	5236.7	98.1	93.7	4.44
Z3	192.848	123.725	-185.411	-102.160	7436.8	21564.3	103.0	95.0	8.00
Z4	69.570	6.306	-68.867	-4.893	703.4	1413.0	95.0	93.8	1.17
Z5	55.841	55.855	-54.458	-51.293	1382.4	4561.9	95.0	90.0	5.02
Z6	2.268	-8.669	-2.258	8.719	9.9	49.6	90.0	90.4	0.46
<b>Z</b> 7	89.073	73.454	-86.947	-68.493	2125.7	4960.5	93.8	89.7	4.13
Z8	6.947	8.493	-6.899	-8.379	47.9	113.7	89.7	88.7	0.97
					18670.0	47381.0			

<sup>\*</sup> This Transmission Line includes Series Capacitor.

Location: 19.0.1C Date: 08-01-2021

SN:

Base

Engineer: Revision:

Contract:

Filename: Study Case: LF Revision: Base

Study Case: LF

Config.: Normal

## **Alert Summary Report**

## % Alert Settings

	Critical	Marginal
<b>Loading</b>		
Bus	100.0	95.0
Cable / Busway	100.0	95.0
Reactor	100.0	95.0
Line	100.0	95.0
Transformer	100.0	95.0
Panel	100.0	95.0
Protective Device	100.0	95.0
Generator	100.0	95.0
Inverter/Charger	100.0	95.0
Bus Voltage		
OverVoltage	105.0	102.0
UnderVoltage	95.0	98.0
<b>Generator Excitation</b>		
OverExcited (Q Max.)	100.0	95.0
UnderExcited (Q Min.)	100.0	

## **Critical Report**

Device ID	Туре	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus 3	Bus	Under Voltage	11.000	kV	10.302	93.7	3-Phase
Bus 4	Bus	Under Voltage	11.000	kV	10.450	95.0	3-Phase
Bus 5	Bus	Under Voltage	11.000	kV	10.322	93.8	3-Phase
Bus 6	Bus	Under Voltage	11.000	kV	9.898	90.0	3-Phase
Bus 7	Bus	Under Voltage	11.000	kV	9.868	89.7	3-Phase
Bus 8	Bus	Under Voltage	11.000	kV	9.761	88.7	3-Phase
Bus 9	Bus	Under Voltage	11.000	kV	9.948	90.4	3-Phase
Gen2	Generator	Overload	80.000	MW	80.000	100.0	3-Phase
Gen2	Generator	Over Excited	49.580	Mvar	94.118	189.8	3-Phase

# **Marginal Report**

	Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type	
Bus1		Bus	Over Voltage	11 000	kV	11 330	103.0	3-Phase	_

Location: 19.0.1C Date: 08-01-2021

SN:

Engineer: Study Case: LF Revision: Base

Config.: Normal

## SUMMARY OF TOTAL GENERATION, LOADING & DEMAND

	MW	Mvar	MVA	% PF
Source (Swing Buses):	283.033	187.938	339.747	83.31 Lagging
Source (Non-Swing Buses):	80.000	94.118	123.524	64.76 Lagging
Total Demand:	363.033	282.056	459.726	78.97 Lagging
Total Motor Load:	341.091	233.039	413.098	82.57 Lagging
Total Static Load:	3.272	1.636	3.658	89.44 Lagging
Total Constant I Load:	0.000	0.000	0.000	
Total Generic Load:	0.000	0.000	0.000	
Apparent Losses:	18.670	47.381		
System Mismatch:	0.000	0.000		

Number of Iterations: 4

Contract:

Filename:

NEW\_PSA